

Maintenance

SPACE

SHELTER

STORAGE



Aliport Commercial offer a number of after-care packages whereby a fitter will visit your location on a regular basis and undertake routine maintenance and cleaning of your canopy as required to work alongside and extend the length of the warranty. Please contact us should you wish to discuss after-care of your installation.

Cleaning

Framework

The powder coated aluminium surface shall be cleaned when required using a solution of mild soap and lukewarm water, using a soft cloth or sponge. Do not use abrasive detergents and cleaners or sharp instruments as this may result in scratches to the finish of the Framework

Roofing

The roofing panels shall be cleaned when required using a solution of mild soap and lukewarm water, using a soft cloth or sponge. Do not use abrasive detergents or cleaners or sharp instruments as this may result in scratches to the roofing panels

Post Protectors

The post protectors shall be cleaned when required using a solution of mild soap and lukewarm water, using a soft sponge or cloth. Do not use abrasive detergents or cleaners or sharp instruments as this may result in scratches to the post protector

Rainwater Goods

The Rainwater Goods shall be cleaned when required using a solution of mild soap and lukewarm water, using a soft sponge or cloth. Do not use abrasive detergents or cleaners or sharp instruments as this may result in scratches to the finish.

Please ensure that all rainwater goods are kept clear to avoid a build-up of debris that can cause blockages



Access

Framework

Access to the framework for cleaning shall be via a mobile scaffold tower or similar positioned underneath the structure

Roofing

Access to the roof panels for cleaning shall be via either a mobile scaffold tower or a cherry picker. We do not recommend placing any load upon the roof panels for the purposes of cleaning

Rainwater Goods

Access to the rainwater goods for cleaning shall be via a mobile scaffold tower or similar positioned in front of the structure

Please ensure any access equipment is checked and certified prior to use and that all operators are qualified to operate and / or erect